

**WBSEDCL****WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED**

(A Government of West Bengal Enterprise)

OFFICE OF THE DIRECTOR (DISTRIBUTION)A-BLOCK, 7TH FLOOR, VIDYUT BHAWAN, BIDHANNAGAR, KOLKATA- 700091e-mail: dirdist@wbsecl.in. TEL (033) 23591891, FAX (033) 23345607,Website www.wbsecl.in, CIN NO: U40109WB20075GC113473

OFFICE ORDER NO:- 73

DATE:- 27.01.2026

Sub:- Store Testing Protocol for Unsealed Materials, Cable & Conductors Procured from P&C Dept.

It came to our notice that in recent past, there is increase in frequent & untimely failure of material causing outage and hampering consumer service. To ensure the right quality of the material inspected at factory premises is being delivered to WBSEDCL, store testing is the only option to deal with. The Procurement and Contracts Department along with Distribution Testing Department have also agreed to the necessity of introducing Store Testing for all major items used in Distribution O&M and procured centrally from P&C Dept.

Following action plan has been formulated in order to ensure quality of the materials specially unsealed items along with Cables & Conductors:-

1. Store testing details have to be mentioned explicitly in the upcoming NITs and Purchase Orders along with details of sampling as per relevant IS/IEC as well as prevailing practice of WBSEDCL.

Action-P&CD

2. Numbers of block available in the LA has to be verified at factory during material inspection to match with TS of WBSEDCL and subsequently to be re-checked at the respective stores upon delivery. Necessary instruction is to be mentioned in respective NIT.

Action-P&CD

3. **Sample Sealing & Despatch** -Sufficient quantity of samples i.r.o LA/Insulators/Isolators/Hardware fittings etc. is to be sealed during FAT so that at least two samples shall be sent to each of the Consignee locations during delivery of material. Necessary instruction should be given during issuance of Despatch instruction.

Action-P&CD

4. **Cable Length Measurement** – Rate Contracts for LT cables and LTAB cables are to be finalized in line with ACSR conductor length measurement. Zonal Managers to place separate P.Os for measuring cable length for all kind of LT and LTAB cable in line with the ACSR conductor length measurement.

Action-P&CD & Zonal Manager

5. **Zonal Inspection Committee Formation**- Zonal Managers to form one three member Inspection Committee consisting of Store In Charge, dealing S.E/D.E from Zone and with one engineer (as per discretion of Zonal Manager) preferable from Zonal Testing Wing. **Kolkata Zonal Inspection Committee will take up inspection activity after delivery of material at CRCS along with Kolkata Zonal Store as being followed for DTRs.**

Action- Zonal Manager

6. It has been decided that for measurement of conductor resistance for cables, manufacturer's representative along with suitable instruments/arrangement for cutting of insulation, taking out leads, termination, sealing is to be present during testing. Necessary instruction is to be given from Store to the vendors in advance.

Action – Zonal Store/CRCS

7. Till store testing set up is ready at Zonal Level, P&C Dept. may take action to conduct some tests (as part of store testing procedure) from NTH/NABL Accredited Laboratory as per requirement in the interim period.

Action-P&CD



WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

(A Government of West Bengal Enterprise)

OFFICE OF THE DIRECTOR (DISTRIBUTION)

A-BLOCK, 7TH FLOOR, VIDYUT BHAWAN, BIDHANNAGAR, KOLKATA- 700091

e-mail: dirdist@wbsecl.in. TEL (033) 23591891, FAX (033) 23345607,

Website www.wbsecl.in, CIN NO: U40109WB2007SGC113473

WBSEDCL

8. Store Test is to be conducted for the following items after delivery of material at Zonal Store/CRCS as detailed below before drawal of SRV. Sampling will be governed by relevant IS/IEC as well as prevalent practice of WBSEDCL against each item.

Sl. No.	Item	Tests to be conducted at Store	Third Party NABL /Govt. Lab.	Responsibility to carry out Store Testing
i.	11KV & 33KV Pin Insulator	1. Dimensional Checking - verification with sealed Item obtained from FAT. 2. Galvanization Thickness Test of metallic end fittings by Elcometer.	Not Required	Inspection Committee at Zonal Level
ii.	11 KV & 33 KV Disc Insulator	1. Dimensional Checking - verification with sealed Item obtained from FAT. 2. Verification of the Specified Mechanical Load by Universal Testing Machine 3. Galvanization Thickness Test of metallic end fittings by Elcometer.	-----do-----	
iii.	11KV & 33 KV Post Insulators	-----do-----	-----do-----	
iv.	33 KV & 11KV Lighting Arrestors	1. Dimensional Checking - Verification with sealed Item obtained from FAT. 2. Block verification (no. of blocks) for 33KV LA to commensurate FAT report.	-----do-----	
v.	11 KV TPGO & 33 KV CR type Isolators	1. Dimensional Checking - Verification with sealed Item obtained from FAT for male female contacts, flexible chord, Connectors. 2. Weight for flexible chord, male, female contact.	-----do-----	
vi.	GI Wires and Stay Wires	1. Dimension Verification 2. Galvanization Thickness Test of metallic end fittings by Elcometer.	-----do-----	
vii.	GI Stay Set & earth Spike	1. Verification of the Specified Mechanical Load by Universal Testing Machine 2. Galvanization Thickness Test of metallic end fittings by Elcometer.	-----do-----	
viii.	HT cables (Sealed)	1. Physical Dimension 2. Conductor Resistance Test by Mili Ohm Meter.	-----do-----	
ix.	LT cables (Sealed)	1. Physical Dimension 2. Conductor Resistance Test by Mili Ohm Meter 3. Cable Length (if set up is available)	---do---	
x.	LTAB Cable(Sealed)	1. Conductor Resistance Test for messenger wire and conductor by Milli Ohm Meter. 2. Breaking Load of Messenger Wire by UTS Machine 3. Cable Length (if set up is available)	-----do---	



WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

(A Government of West Bengal Enterprise)

OFFICE OF THE DIRECTOR (DISTRIBUTION)

A-BLOCK , 7TH FLOOR, VIDYUT BHAWAN, BIDHANNAGAR, KOLKATA- 700091

e-mail: dirdist@wbasedcl.in. TEL (033) 23591891, FAX (033) 23345607,

Website www.wbasedcl.in, CIN NO: U40109WB2007SGC113473

WBSEDCL

		4. Physical Dimension	
xi.	Conductors (Sealed)	1. Verification of No. of strands and strand diameter. 2. Conductor Resistance Test. 3. Verification of the Specified Mechanical Load by Universal Testing Machine.	-----do---
xii.	Composite Hardware fittings for Panther, Wolf, Rabbit and Dog conductors	1. Dimensional checking - Verification with sealed Item obtained from FAT. 2. Verification of the Specified Mechanical Load by Universal Testing Machine. 3. Galvanization Thickness Test of metallic end fittings by Elcometer.	Microstructure of Metallic End fittings (IS 4748:2009 & IS 2004:1991) - in any Lot as per discretion of respective Zonal Inspection Committee

9. Store testing equipment & instruments is to be installed at respective Zonal Stores & CRCS for early testing. In case, there is any shortage of enclosed space, necessary action is to be taken from Zone end.

Action-Zonal Manager


10. Procurement of the following store testing equipment to be used by different Zonal Testing Wing /Zones will be taken up from DTD for all Zones & CRCS. Necessary budget will be provided from Distribution H.Q. Details of Test Equipments are as below for one set each for each Zone & CRCS:-
- Universal Testing Machine
 - Elcometer

Action – DTD

11. Procurement of the following store testing equipment along with calibration of measuring/testing equipment to be used at Zonal Store will be taken up by respective Zonal Manager. Kolkata Zone will arrange to procure following equipment to be used in CRCS:-
- Micro Ohm Meter
 - Weighing Machine
 - Resistance Bridge
 - Meggar
 - Digital Screw Gauge, Vernier, Slide Callipers, Standard Resistance Box & any other Tools required for above testing
 - Wire Straightening Machine

Action – Zonal Manager

This Order will take immediate effect.


Director (Distribution)

Distribution:-

1. The Executive Director(Dist.),WBSEDCL.
2. The Chief Engineer(Dist.-North/Dist. South)/P&C/DTD/P&E,WBSEDCL
3. **The Zonal Manager (s)**
Kolkata/Burdwan/Siliguri/Berhampur/Midnapur /Malda Zone: WBSEDCL
4. **The Regional Manager (s)**
Bidhannagar/ 24-Prgs.(North)/ 24-Prgs.(South)/ Howrah/ Hooghly/ Purba-Burdwan/Paschim-Burdwan/ Birbhum/ Purba Midnapore/ Paschim Midnapore/ Kalingpong/Bankura/ Purulia/ Malda/ Murshidabad/ Nadia/ Darjeeling/ Jalpaiguri/ Raiganj/Dakhin-Dinajpur/ Coochbehar/ Alipurduar/ Jhargram Regional: WBSEDCL
5. **The Divisional Manager(s):** Behala/Baruipur/Garia/ Diamond Harbour/ Canning/ Bidhannagar-I/Bidhannagar-II/ Howrah-I/ Howrah-II/ Uluberia/ Barrackpore/ Naihati/ Barasat/ Basirhat/Habra/Bongoan/ Serampore/ Singur-Haripal/ Tarakeswar/ Arambag/ Chandannagar/ Mogra/ Kalna/Katwa/Memari/Burdwan North/Burdwan South/ Durgapur/ Asansol/ Suri/ Rampurhat/Bolpur/ Tamluk/ Contai/ Haldia /Ghatal/ Midnapur/ Kharagpur/ Bankura/ Bishnupur/ Purulia/ Raghunathpur/Kalyani/ Krishnagar/ Tehatta/Berhampur/Kandi/ Raghunathganj/ North Malda/ South Malda/Raiganj/ Dakshin Dinajpur/ Jalpaiguri/Domkal/Jiaganj/Alipurduar/ Coochbehar/Darjeeling/SiliguriTown/ Siliguri Suburbon/ Kurseong/Islampur/ Kalimpong/Mal/Mathabhanga/Belda/Egra/Jhargram/Khatra/Nakashipara/ Kakdwip/Bhangar/NewTown/Balurghat/Ranaghat/Joynagar/Baduria Division, WBSEDCL.
6. Sr.P.S to CMD /Director(Project),WBSEDCL