



WBSEDCL

WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

(A Government of West Bengal Enterprise)

CIN : U40109WB2007SGC113473

VIDYUT BHAWAN : BIDHANNAGAR : KOLKATA- 91

DISTRIBUTION HEAD QUARTER, WBSEDCL

Circular No. - 09

Dated: 09.08.2023

Sub: - Pre-puja Maintenance of different installation of the Company for maintaining uninterrupted Power Supply during the ensuing Festive Days

Durga Puja will be held in West Bengal from **20th October (Mahasasthi) to 24th October, 2023 (Bijaya Dasami)** and Kali Puja and Dewali are scheduled from **12th November to 14th November, 2023** and it is required to maintain un-interrupted power supply during these days.

It is needless to mention that it is the responsibility on our part to maintain steady power supply during the above period across the jurisdiction of WBSEDCL. Hence, completion of preventive maintenance of the lines and Sub-Stations before the festival is of paramount importance.

Condition Monitoring of all major equipment at 33/11kV Substations is to be done with the help of Zonal Condition Monitoring teams to ascertain whether there is any Partial Discharge or Hot spot or any other potential fault at those equipment's. Integrity test of Vacuum Interrupter Bottles of 33KV & 11KV Vacuum Circuit Breakers should also be done for important Sub-Stations. Necessary Condition Based Maintenance work is to be carried out as per Condition Monitoring report. Such action taken reports based on observation of Condition Monitoring Team must be sent to respective Condition Monitoring Units with a copy to this end.

In addition to the above, all units under Distribution Wing shall have to follow the following instructions during pre-puja maintenance work.

A. 33 KV System

1. 33/11/6 KV Sub-Station

- i. The IR value of the 33/11 KV transformer is to be checked, and if required, the transformer oil may be changed / filtered.
- ii. Silica gel of the breather is to be properly checked and if required is to be replaced.
- iii. The gaskets of the power transformer should be checked properly and if there is any oil leakage, the gaskets should be replaced. For gasket replacement if the Transformer Top Cover is to be opened, filtration is a must.
- iv. Checking of the level of transformer oil is very much essential and if required topping up of transformer oil is to be done.
- v. The fuse unit should be properly checked and proper gap is to be maintained.
- vi. The connections of the transformer kiosk should be checked properly for proper operation of relays, temperature indicators, buchholz relays etc.
- vii. 33 KV Bus support should be properly checked and to be replaced, if required the clamps of the pipe to be checked properly and if required be tightened / replaced.
- viii. 33KV isolators both vertical and horizontal type are to be checked properly so that there should not be any gap between the male and female contacts to avoid sparking during peak loading period.



WBSEDCL

WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

(A Government of West Bengal Enterprise)

CIN : U40109WB20075GC113473

VIDYUT BHAWAN : BIDHANNAGAR : KOLKATA- 91

DISTRIBUTION HEAD QUARTER, WBSEDCL

33/11 KV Sub-Station Equipment & Apparatus

- i. The I.R. value of the MOCB/ VCB should be checked. In case of low value, proper action is to be taken by replacing oil, spout etc. Optimum I.R. value needs to be achieved.
- ii. The mechanical parts of the MOCB / VCB are to be checked properly and also to be overhauled, if necessary.
- iii. The control circuit of the breaker is to be checked properly for proper operation of the MOCB/VCB by ON / OFF operation (Mechanically/Electrically) and through relay.
- iv. Battery and Battery Charger to be maintained properly.
- v. L.As to be checked and maintained properly.
- vi. All attempts should be given to make the sub-station VHF set ready for operation.

2. 33 KV Overhead line

- i. Jumpering of 33 KV overhead line must be checked and if required new P.G. Clamp is to be connected.
- ii. Proper route clearance is to be maintained by trimming of green plants etc.
- iii. Condition of Conductor is to be checked to ensure proper loading.
- iv. Damaged Cradle Guards are to be replaced. Cradle Guards are to be installed at congested places, road crossings etc., if it is not there.

B. 11 KV System

1. Distribution Sub-Station

- i. The I.R. values of the distribution transformers are to be checked, and if required, transformer oil may be filtered.
- ii. Breather and L.A. in DTR are to be ensured in proper condition. Proper earthing of DTR is also to be checked /ensured.
- iii. Gaskets and the studs of the distribution transformers are to be checked properly and in case of oil leakage the gaskets should be replaced and the damaged studs of transformer are also to be replaced. ,
- iv. Jumpering of the distribution transformers should be checked properly, and if required, the same is to be tightened and sockets and clamps should be replaced.
- v. The fuse units should be properly checked and are to be replaced by new fuse.
- vi. The L.T. kiosk of the transformer should be checked properly and the damaged cut out of the main switch to be replaced by new proper one.
- vii. The load balancing of the transformers is to be done during peak hours.
- viii. For areas like Salt Lake, New-Town etc, where LT underground system exists, the feeder pillar boxes and junction boxes should be checked properly and defective cut outs should be replaced. The L.T. panels of distribution S/S are also to be checked properly and defective main switches and cut outs are to be replaced.



WBSEDCL

WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

(A Government of West Bengal Enterprise)

CIN : U40109WB2007SGC113473

VIDYUT BHAWAN : BIDHANNAGAR : KOLKATA- 91

DISTRIBUTION HEAD QUARTER, WBSEDCL

2. 11KV Overhead/Underground line

- i. The jumpers of the 11 KV overhead lines must be checked.
- ii. Proper route clearance to be maintained by trimming of green plants etc.
- iii. Condition of Conductor is to be checked for proper loading.
- iv. Proper sagging of the overhead line may have to be made, if necessary.
- v. Damaged Cradle Guards are to be replaced. Cradle Guards are to be installed at congested places, road crossings etc., if it is not there.
- vi. Partial Discharge of indoor & outdoor termination is to be measured and remedial measure is to be taken if Partial Discharge is found.
- vii. Earthing of metallic screen of HT AB Cable is to be checked and if necessary corrective action is to be taken.


C. L.T. Overhead/Underground line

- i. Jumpers of L.T. line must have to be checked and where necessary re-jumping may be done.
- ii. Feeder fuse of the L.T. line is to be checked properly, if necessary cut out is to be replaced.
- iii. Route clearance for the overhead line must have to be made by trimming of green plants.
- iv. For underground system the sockets and joints should be checked properly.
- v. Brittle and damaged conductor of the overhead system is to be replaced by new conductor.
- vi. L.T. Cables should be checked and if necessary to be replaced by healthy one.
- vii. Spacers are to be fixed to the L.T. Overhead Lines at congested places, Puja locations and other important areas, before Puja.
- viii. Carbon cleaning in contacts/connections is to be made properly

All the Divisional Managers are hereby advised to send the pre-puja maintenance schedule immediately. Weekly report of work done in this respect is also to be sent through e-mail to Distribution H.Q. If any pre-scheduled programme is not done, reason for such non-execution is also to be mentioned.

Necessary action may be taken for procurement of local items. For Central items the requirement of materials may be sent well in advance so that the pre-puja maintenance work may not hamper.

Additional requirement of HT/LT Mobile vans for maintaining power supply during the festive days is to be assessed and intimated to the undersigned. Special Control Rooms are to be opened at Division, Region & Zones during the festival days and the phone numbers of such Control Rooms along with the mobile numbers of all site officers are to be communicated to all concerned including the local administration.


(S. Mukherjee)

Chief Engineer (Distribution)
WBSEDCL



WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

(A Government of West Bengal Enterprise)

CIN : U40109WB20075GC113473

WBSEDCL

VIDYUT BHAWAN : BIDHANNAGAR : KOLKATA- 91

DISTRIBUTION HEAD QUARTER, WBSEDCL

Memo No: CED/Technical Circular/ 230 (1 to 123)

Dated- 09.08.2023

Distribution:

1. The Director(HR)/ Director(Dist.)/ Director (Finance), WBSEDCL
2. The Chief Engineer, IT&C/ R&EM/Comml/ CRM/ P&E/DTD/ Pocurement and Contract/ RE, WBSEDCL
3. The General Manager (HR&A)/ (F&A), WBSEDCL
4. The Zonal Manager: Kolkata/ Burdwan / Berhampore/ Midnapur/ Siliguri Zone WBSEDCL.
5. The Addl. Chief Engineer-I, Dist. H.Q., WBSEDCL
6. The Addl. General Manager (HR&A), Dist. H.Q., WBSEDCL
7. The Addl General Manager (HR & A), Board Cell, **May kindly arrange to upload at Company's website.**
8. The Addl Chief Engineer-I/II/III, Dist. H.Q., WBSEDCL
9. The Regional Managers: Bidhannagar/ North 24 Parganas/ South 24 Parganas/ Howrah/ Bankura/Purulia/PurbaMidnapur/PaschimMidnapur/Birbhum/Hooghly/PurbaBurdwan/PaschimBurdwan/Jalpaiguri/Darjeeling/Raiganj/Coochbehar/Alipurduar/DakshinDinajpur(Balurghat)/Malda/ Murshidabad/ Nadia Region, WBSEDCL
10. The Divisional Managers: Alipurduar/ Arambagh/Asansol/ Bankura/ Barrackpore/ Barasat/ Baruipur/Joynagar/ Basirhat/ Behala/Bhangar/ Berhampore/ Bidhannagar-I /Bidhannagar- II /Bishnupur / Bongaon/ Bolpur/ Belda / Burdwan Urban / Burdwan Rural/ Buniadpur/ Canning / Chandannagar / Contai/ Coochbehar / DakshinDinajpur /Darjeeling/ Diamond Harbour / Domkal/ Durgapur/Dinhata/ Egra/ Garia/ Ghatal/ Habra/ Haldia/ Howrah-I/ Howrah- II /Islampur /Jalpaiguri /Jhargram/ Jiaganj/ Kakdwip/ Kalna/ Kalyani/ Kandi/ Katwa/ Kharagpur/ Krishnanagar/ Khatra / Kurseong / Kalimpong /Mal/ Memari/ Midnapur / Mogra/ Naihati/ Nakasipara/North Malda/New Town/ Purulia/ Raghunathpur / Raghunathganj/ Rampurhat /Ranaghat/Raiganj/ Serampore/ Singur-Haripal/South Malda/ Mathabhanga /Suri/ Siliguri Town/ Siliguri Suburban/ Tamluk/ Tarakeswar/ Tehatta /Uluberia Division, WBSEDCL

- **For necessary action and circulation to the Station Managers & AE/DE (Tech) concerned.**