



West Bengal State Electricity Distribution Company Limited
(A Govt. Of West Bengal Enterprise)



TECHNICAL SPECIFICATION OF LT RING TYPE, SINGLE PHASE SINGLE RATIO,
POLYCARBONATE ENCAPSULATED DRY TYPE CURRENT TRANSFORMERS
OF RATIO 200/5A, 400/5A.

JANUARY'2026

Am
20.02.26
Superintending Engineer (E)
Procurement & Contract Deptt.
WBSEDCL
Vidyut Bhavan, Kolkata-700 091

TECHNICAL SPECIFICATION OF LT RING TYPE POLYCARBONATE ENCAPSULATED DRY TYPE LT CURRENT TRANSFORMERS

Page 10/18

**INDEX**

Sl. No.	Contents
1.	Scope
2.	System Particulars
3.	Service Conditions
4.	Applicable Standards
5.	Principle Technical Parameters of Current Transformers
6.	General Technical Requirements of Current Transformers
7.	Tests
8.	Inspection
9.	Qualifying requirements
10.	Quality Assurance Plan
11.	Performance Guarantee
12.	Documentation
13.	Packing and Forwarding
14.	Information to be filled/furnished in variably by Bidder
15.	Guaranteed Technical Particulars
16.	Schedules
ANNEXURE	
1.	Annexure A: Principle Technical Parameters of LT Polycarbonate Encapsulated Dry Type, Single Phase, Single Ratio type Current Transformers. Annexure B : Current Transformer rating plate
SCHEDULE	
1.	SCHEDULE "A"-Guaranteed Technical Particulars of LT Polycarbonate Encapsulated, Dry Type, Single Phase, Single Ratio type Current Transformers.
2.	SCHEDULE "B"-List of Type Test Reports to be enclosed with the offer
3.	SCHEDULE "C"-Schedule of Deviations from Specification



Technical Specification of LT Polycarbonate Encapsulated Dry Type, Single Phase, Single Ratio type Current Transformers

1.0 Scope:-

- 1.1 This specification covers design, manufacture, assembly, testing before supply, inspection, packing and delivery and other basic technical requirements in respect of LT ring type, Polycarbonate Encapsulated, Dry Type, Single Phase, Single Ratio type Current Transformers to be installed at various site in WBSEDCL. The current transformer will be used with poly phase energy meters for measuring energy. The Current Transformers for Metering to be supplied against this specification are required for vital installations where continuity of service is very important. The design, materials and manufacture of the Current Transformers shall, therefore, be of the highest order to ensure continuous and trouble-free service over the years.
- 1.2 The Current Transformers for Metering offered shall be complete with all parts necessary for their effective and trouble-free operation. Such parts will be deemed to be within the scope of the supply irrespective of whether they are specifically indicated in the commercial order or not.
- 1.3 It is not the intent to specify herein complete details of design and construction. The Current Transformers for Metering offered shall conform to the relevant standards and be of high quality, sturdy, robust and of good design and workmanship complete in all respects and capable to perform continuous and satisfactory operations in the actual service conditions at site and shall have sufficiently long life in service as per statutory requirements.

2.0 System Particulars:-

2.1 Nominal System Voltage	:433V
2.2 Highest System Voltage of the equipment	:0.72 kV
2.3 Voltage variation on supply side	:±10%
2.4 Basic Insulation Level	:3 kV rms
2.5 Rated Frequency	:50HZ with ± 3% tolerance
2.6 Number of phases	:3Phases
2.7 Neutral Earthing	:Solidly Effectively Earthed



3.0 Service Conditions:-

A) The Polycarbonate Encapsulated Dry Type, Single Phase, Single Ratio type Current Transformers for Metering to be supplied against this specification shall be suitable for satisfactory continuous operation under the following tropical conditions.

The climatic and isoceraunic conditions at site are given below :

- (a) Max. Ambient temp : 45 °C
- (b) Minimum ambient temp : 4°C
- (c) Maximum relative humidity : 100%
- (d) Average number of thunderstorm day per annum : 75
- (e) Max. No. of rainy days/annum : 120 days
- (f) Average Rainfall : 1000 mm. to 3000 mm.
- (g) Max. Wind pressure/wind speed : 150 Kg. Per Mtr. sq
- (h) Height above sea level(m) not exceeding : 1000
- (i) Earthquake acceleration horizontal seismic co-efficient : As per IS:1893(1984)

For Class-III & IV Zones

B) The climatic conditions are prone to wide variations in ambient conditions and Moderately hot and humid tropical climate, conducive to rust and fungus growth. Hence, the Current Transformers for Metering shall be of suitable design to work satisfactorily under these conditions.

4.0 Applicable Standards:-

- 4.1 The design, manufacture and performance of the Current Transformers for Metering shall comply with all currently applicable statutes, regulations and safety codes. Nothing in this specification shall be construed to relieve the bidder off his responsibilities.
- 4.2 Unless otherwise specified, the Current Transformers for Metering offered shall conform to the latest applicable Indian, IEC, British, U.S.A. or International Standards and in particular, to the following:-

Sr. No.	Standards	Particulars
1.	IS 2165	Insulation coordination of highest voltages for equipments
2.	IS16227(Part-1)/(Part-2)/2016	Current Transformers
3.	IS3202	Code of practice for climate proofing of electrical equipments
4.	IS2071	Method of high Voltage Testing
5.	IEC185	Current Transformers



5.0 Principal Technical Parameters of Current Transformers:

The equipment covered under this specification shall conform to specific parameters given below:

5.1 Principal Technical Parameters of Current Transformers for Metering

- i) Type of CT : LT Polycarbonate Encapsulated, Dry Type, single Phase, Single Ratio type Current Transformer
- ii) Inner Diameter : Not less than 45 mm. Suitable for mounting through 40 X 10 Sq mm flat bar.
- iii) Outer Diameter : Not greater than 100 mm.
- iv) Nominal System Voltage : 0.433kV
- v) CT Rated operating Voltage : 0.44kV
- vi) Highest System Voltage : 0.72kV
- vii) Frequency : 50Hz with $\pm 3\%$ tolerance
- viii) Neutral Earthing : Solidly Effectively Earthed
- ix) One minute dry/wet power frequency Withstand Voltage(kV rms) : 3 kV
- x) Rated Short Time Withstand Current : 5 kA for 1 second
- xi) Rated Dynamic Withstand Current(kAp) : 2.5 Times STC
- xii) Instrument Security Factor : 5 or less
- xiii) Class of Insulation : E or better
- xiii) Rated Continuous Thermal Current(A): 120% of the rated Primary current
- xiv) Temperature rise : As per IS: 16227(Part-1) & IS: 16227 (Part-2) 2016
- xv) Single Core : Metering
- xvi) CT Ratio : 200/5A, 400/5A
- xvii) Burden : 5VA
- xviii) Class of Accuracy : 0.5S



6.0 General Technical Requirements of Current Transformers:-

6.1 Polycarbonate Encapsulated Assembly:-

Encapsulation: Polycarbonate (Flame retardant, self-extinguishing, high mechanical strength).

The Current Transformer shall be **fully encapsulated** in high-grade, **polycarbonate** material. The polycarbonate used shall be **flame-retardant, non-hygroscopic, moisture-resistant and resistant to tracking, ageing and environmental degradation.**

The encapsulation shall be of **single-piece, joint-less moulded construction**, free from cracks, voids or seams, and shall provide **adequate mechanical strength, dielectric insulation and thermal stability** suitable for continuous operation under tropical Indian climatic conditions.

Type: Ring Type.

6.2 Insulation Material:-

Insulation Material used for Current Transformer should be Polycarbonate having Insulation Class E or better. The dielectric withstand values specified in this specification are meant for fully assembled Current Transformer. The temperature rise on any part of equipment shall not exceed the maximum temperature rise limits specified in relevant IS.

6.3 Name Plate and Rating Plate:-

The rating and Terminal Marking of the CT shall Embossed markings or printed. The aesthetics and layout of the rating plate shall be approved.

6.4 Secondary Winding:-

- i) Suitably insulated copper wire of electrolytic grade/Super Enameled as per IS 4800 shall be used for Secondary Windings. Type of insulations used shall be described in the offer. The cross section area of Secondary Winding, number of Secondary Turns, Current Density etc. shall be mentioned by the bidder.
- ii) The excitation current of the CT shall be as low as possible.

6.5 Core : The Core material of CTs shall be high grade non ageing electric low loss core.

6.6 Secondary Terminals:-

1. Properly insulated long lead Enameled copper Secondary wires (without any joint in between and having continuous current carrying capacity of at least 10 Amp) measuring at least 1.5 meters (Red colour for S1 & Black colour for S2) are to be provided for secondary connection. These secondary leads will have to be drawn out from inside the secondary winding insulation of the CT in such a way that no joint is visible or accessible from outside.
2. Polarity (both for primary side and secondary leads) shall be marked.



- 6.7 Current Transformer characteristic shall be such as to provide satisfactory performance for burdens ranging from 25% to 100% of rated burden over a range of 1% to 120% of rated current in metering CTs. Polarity shall be invariably marked in each Primary and Secondary terminal. The Instrument Security Factor of metering core shall be less than 5. This shall be demonstrated on all the ratios of metering core in accordance with procedure specified in IEC-185 or IS-16227-2016.

7.0 Tests:

A) Type Test:

The bidder shall submit complete test reports of all tests (including Type Test) as stipulated in relevant IS-16227 with Complete identification, date and serial no., carried out in CPRI/ NABL accredited/ Government recognized Test House or Laboratory on tendered item/items. These Type Tests should have been carried out within five years/latest CEA guidelines prior to the date of opening of tender. The bidder shall be required to submit complete set of the type test reports along with the offer.

Type Tests:

- 1) Power frequency voltage Withstand Test.
- 2) Verification of terminal marking and polarity.
- 3) Temperature Rise Test
- 4) Tests for accuracy
- 5) Short Time Current Test and peak dynamic current test.
- 6) Over voltage interturn test.

B) Acceptance & Routine Tests:-

All acceptance tests as stipulated in the respective applicable standards amended up-to-date for current transformer shall be carried out by the supplier in the presence of purchaser's representative without any extra cost to the purchaser before dispatch.

The bidder shall have full facilities to carry out all the acceptance and routine test as per the applicable standards.

C) MINIMUM TESTING FACILITIES

The manufacturer shall have following testing facilities for carrying out routine and acceptance tests as mentioned in earlier clauses.

- a) Automatic CT Test set-up (duly calibrated by NABL Accredited laboratories as applicable) for ratio error and phase angle error measurement.
- b) Burden Box.
- c) High voltage tester.
- d) Test facility for over-voltage inter-turn testing.
- e) The manufacturer shall possess duly calibrated Standard CT of Class 0.05



accuracy or better.

- i) The manufacturer shall submit the list of testing facilities available with him.

After finalization of the program of type/acceptance/routine testing, the supplier shall give 15 days advance intimation to the purchaser, to enable him to depute his representatives for witnessing the tests.

D) Acceptance & Routine Tests:

- 1) Power frequency voltage Withstand Test.
- 2) Tests for accuracy.
- 3) Verification of terminal marking and polarity.
- 4) Determination of the secondary winding resistance.
- 5) Determination of the ISF.
- 6) Interturn over voltage test.

E) Sample Approval:

Two nos sample of offered CT are to be submitted to Chief Engineer (Distribution Testing Department), Abhikshan Bhavan, Kolkata for routine test approval.

8.0 Inspection:-

- i) The inspection may be carried out by the purchaser at any stage of manufacture. The successful bidder shall grant free access to the purchaser's representative at any reasonable time when the work is in progress. All facilities must be made available by supplier/ manufacturer for unrestricted inspection of the works, raw material & manufacture of all the accessories & for conducting necessary tests as declared therein.
- ii) No current transformer shall be dispatched from its point of manufacture unless the current transformer has been satisfactorily inspected and tested.
- iii) Inspection and acceptance of any current transformer under this specification by the purchaser shall not relieve the supplier of his obligation of furnishing current transformer in accordance with the specification and shall not prevent subsequent rejection, if the current transformer is found to be defective.

9.0 Quality Assurance Plan :-

- i) In case of new vendor, WBSEDCL's standard procedure to be followed.

10.0 Performance Guarantee:

The equipment offered shall be guaranteed for satisfactory performance for a period of 60 months from the date of receipt of complete equipment at site in good condition. In case of failure within this period, the supplier shall make necessary repairs/replacement of the faulty current transformer at no extra cost to the purchaser.

**11.0 Documentation:-****A) List of Drawings & Documents:-**

The bidder shall furnish two sets of the following drawings alongwith his offer.

- a) General outline and assembly drawings of the equipment
- b) Graphs showing the performance of Current Transformer in regard to Magnetization Characteristic.
- c) Sectional views showing:-
 - i) General Constructional features of Current Transformer, size of conductor, it's cross section.
 - ii) The insulation, the winding arrangements, method of connection of the primary / secondary winding to the primary / secondary terminals etc.
- d) Arrangement of secondary Terminal
- e) Name Plate
- f) Schematic drawing
- g) Type Test reports.
- h) Bill of material and packing list.

B) The successful bidders/suppliers shall submit three sets of final versions of all the above said drawings in line with Technical Specifications & Drawings attached for purchaser's approval after placement of order.

C) The manufacturing of the current transformers shall be strictly in accordance with the approved drawings and no deviation shall be permitted without the written approval of the purchaser. All manufacturing and fabrication work in connection with the current transformers prior to the approval of the drawing shall be at the supplier's risk.

D) Approval of drawings by purchaser shall not relieve the supplier of his responsibility and liability for ensuring correctness and correct interpretation of the drawings for meeting the requirement of the Technical Specification, latest revision of applicable standards, rules and codes of practices. The equipment shall conform in all respects to high standards of engineering, design, workmanship and latest revisions of relevant standards at the time of ordering and purchaser shall have the power to reject any work or materials which, in his judgment, is not in full accordance there with.

12.0 Packing & Forwarding :-

- i) The current transformers shall be packed in crates of good quality and shall be suitable for vertical/horizontal transportation as the case may be, and suitable to withstand handling during transport and storage in stores before erecting.



The supplier shall be responsible for any damage to the equipment during transit, due to improper and inadequate packing. The easily damageable material shall be carefully packed and marked with the appropriate caution symbols. Wherever necessary, proper arrangement for lifting, shall be provided. Any material found short inside the packing cases shall be supplied by supplier without any extra cost.

ii) Each consignment shall be accompanied by a detailed packing list containing the following information:

- a) Name of the consignee
- b) Details of consignment
- c) Destination
- d) Total weight of consignment
- e) Sign showing upper/lower side of the crate
- f) Handling and unpacking instructions
- g) Bill of material indicating contents of each package

14.0. Information to be filled/furnished invariably by Bidder:

The offer shall be complete in all respects, failing which the same are liable for rejection. Guaranteed technical particulars for current transformer shall be elaborate and complete in all respects. It may be noted that the technical evaluation of the tender is made mainly based on the guaranteed technical particulars and deviations from the specifications furnished along with the technical offer.

15.0 Guaranteed Technical Particulars:

The bidder should fill up the details in schedule A-"Guaranteed Technical Particulars" and the statement such as "as per drawing enclosed", "as per WBSEDCL requirement", "as per IS", "as per specification" etc. shall be considered as details not furnished and such offers will be rejected.

16.0 Schedules:-

The bidder shall fill in the following Schedule which forms part of the Tender Specification and offer. If the schedules are not submitted duly filled in with the offer, the offer shall be liable for rejection.

SCHEDULE- "A"- Guaranteed Technical Particulars of LT Polycarbonate Encapsulated Dry Type, Single Phase, Single Ratio type Current Transformers for Metering.

SCHEDULE - "B" - List of Type Test Reports to be enclosed with the offer.

ANNEXURE-A
Principal Technical Parameters of LT Polycarbonate Encapsulated Dry Type, Single Phase, Single Ratio type Current Transformers for Metering

Sr. No.	Item	Specification
1.	Type of CT/Installation	Polycarbonate Encapsulated, Dry Type, Single Phase, Single Ratio type Current Transformer
2.	Suitable for frequency	50Hz with $\pm 3\%$ tolerance
3.	Method of Earthing system to be connected to	Solidly Effectively Earthed
4.	Rated Continuous Thermal Current(A)	120% of the rated Primary current
5.	Acceptable limit of temperature rise above the specified ambient temperatures for continuous operation at rated current	As per IS: 16227(Part-1) & IS:16227(Part-2) 2016
6	CT Ratio	200/5A, 400/5A
7	VA Burden	5 VA
8	Class of Accuracy	0.5S
9.	Rated Voltage/HSV(kV rms)	0.44/0.72
10.	One minute dry/wet Power frequency Withstand Voltage (kV rms)	3 kV
11.	Rated Short Time Withstand Current for 1 Second duration (kArms)	5 kA
12.	Rated Dynamic Withstand Current for 1 Second duration (kAp)	2.5TimesSTC
13.	Power Frequency Over Voltage Withstand requirement for Secondary Winding (kV rms)	3kV
14.	Instrument Security Factor	5 or less
15	Inner Diameter	Not less than 45mm
16	Outer Diameter	Not greater than 100 mm



ANNEXURE-B

Current Transformer rating plate

CURRENT TRANSFORMER	
AS PER IS: 16227	
RATIO:	
MONTH & YEAR OF MFG:	MM/YYYY
SL. NO.:	TYPE: LT ODCT
Rated Voltage(kV) / HSV (kVrms)	:0.440/0.72
RATED CONT. TH. CURRENT: 1.2 X RATED PR. CURRENT	INSULATTON CLASS : E
S T C (th): 5 kA for 1 sec.	DYNAMIC CURRENT : 12.5 kAp
VA: 5	CLASS: 0.5 S
ISF <=5	FREQ. :50 HZ
GUARANTEE PERIOD: 5 YRS	PROJECT:
PROPERTY OF WBSEDCL	
PO No.:	
MFG NAME:	

**SCHEDULE 'A'****Guaranteed Technical Particulars of LT****Polycarbonate Encapsulated Dry Type, Single Phase, Single Ratio type Current Transformers for Metering**

Sr. No.	Particular of GTP Parameter	To be furnished by bidder
1.	Manufacturer's Name & address	
2.	Type of equipment	
3.	Equipment Conforming to Standards	
4.	Rated Voltage / Highest System Voltage in KV	
5.	Rated Primary Current(Amp)	
6.	Rated Secondary Current(Amp)	
7.	Frequency(HZ)	
8.	Ratio of Current Transformer	
9.	Details of Cores	
i)	Number of Cores	
ii)	Purpose	
iii)	Burden(VA)	
iv)	Class of Accuracy	
10.	Rated Short Time Withstand Current For 1 Sec. duration	
11.	Rated Dynamic Withstand Current (KAp)	
12.	One minute Power Frequency Withstand Voltage (KV rms) of Secondary Winding	
13.	Total Weight (KG)	



14.	Overall dimension	
15.	Magnetization Curves are submitted?(Y/N)	
16.	Type of Winding	
17.	Material of Winding	
18.	No. of Secondary Turns	
19.	Current Density of Secondary Winding	
20.	Type of Insulation	
21.	Whether Current Transformer Confirms to Temperature Rise limits.	
22.	Whether Type test reports(within five years) as per Technical Specification are submitted?(Y/N)	
23.	Whether Drawings are submitted along with the offer? (Y/N)	
24.	Rated continuous Thermal Current (120% of the rated Primary Current)	
25.	Instrument Security Factor (ISF ≤ 5)	
26.	Class of Insulation	
27.	Inner diameter	
28.	Outer diameter	
29.	Whether Polycarbonate Encapsulated	

**SCHEDULE 'B'****List of Type Test Reports to be enclosed with the offer**

Sr. No.	Description of Type Test	Type & Make of Current Transformer & its rating	IS/IEC Clause No.	Testing Lab. & Date of Testing	Type test Report No., Dt & pages	Whether Certificate of compliance With IS/IEC is enclosed With T.R.
LT Polycarbonate Encapsulated Dry Type Current Transformers						
1.	Temperature Rise Test					
2.	Power frequency voltage Withstand Test.					
3.	Tests for accuracy					
4.	Short Time Current Test					

Name of the manufacturer_____

Signature of the bidder_____

Designation_____

Date_____



'SCHEDULE 'C'
Schedule of Deviations from Specification

Sr. No.	Clause No.	Details of Deviations
1.		
2.		
3.		
4.		
5.		
6.		
7.		
8.		

Name of the manufacturer_____

Signature of the bidder_____

Designation_____

Date_____



Office of the Chief Engineer
Distribution (P & E) Department

Minutes of the Meeting of the Standardization Committee reconstituted on 19/09/2023 vide Office Order No. 117 by the Director(Distribution) held on 27th January, 2026 at the Conference Room of DHQ, 1st floor, 11 Block, Vidyut Bhavan.

Agenda 1: Incorporation of IR Window in 11KV Switchgear Panel-

Proposed Modifications:

Installation of IR Window (a specially designed transparent port installed on switchgear panels) in 11KV switchgear panel will allow infrared thermography inspection of live electrical components without opening the panel.

Discussions:

- CESC Ltd. has already implemented IR window-based thermographic inspection in its switchgear panels. A few 33/11 kV substations of WBSEDCL had also adopted this practice earlier.
- Incorporation of IR windows may create challenges in maintaining the specified IP protection class of the switchgear enclosure.
- Ensuring compliance with internal arc fault withstand (IAC) test requirements with the inclusion of IR windows may also be technically difficult.

Resolution of the Committee:

- All technical aspects shall be discussed in detail with different OEMs, with specific focus on the parameters that may be compromised due to such incorporation.
- Potential technical solutions and design mitigations proposed by the OEMs to address these compromises shall also be thoroughly examined.
- In addition to 11 kV switchgear panels, the feasibility and implications of incorporation in 33 kV panels shall also be comprehensively discussed.

Agenda 2: Modification of Technical Specification of 11KV XLPE Cable -

Proposed Modifications:

Incorporation of steam curing method in addition to the existing dry inert gas curing within the specification of 11 KV XLPE Cable to include more manufacturer in the tendering process.

Discussions:

- Despite the theoretical consideration that, steam curing is comparatively more hygroscopic than nitrogen curing, the type test reports reveal that all critical performance parameters, including partial discharge, $\tan\delta$, and volume resistivity complies the stipulated permissible limits. Accordingly, on the basis of available and verifiable test evidence, no adverse impact on cable performance can be inferred at this stage. At the same time assessment of performance degradation over several years of continuous operation is presently not feasible.
- In the Indian context, some DISCOMs, such as Assam Power Distribution Company Ltd. (APDCL), North Bihar Power Distribution Company Ltd., currently permit steam curing.

Registered Office: Vidyut Bhavan, Block 52J, Sector -II, Salt Lake City, Kolkata - 700 091

WBSEDCL



alongside dry and gas curing processes in their respective technical specifications for 11kV XLPE power cables.

Resolution of the Committee:

1. steam curing may be considered within the technical specifications of WBSEDCL, its application should be strictly limited to cables up to 11 kV (E) only.
2. Furthermore, the adoption of triple-extrusion technology should be made mandatory, ensuring simultaneous extrusion of conductor screen, insulation, and insulation screen layers to minimize moisture ingress, reduce interfacial contamination, and improve overall insulation integrity.
3. All the technical parameters of the cable will remain same.
4. The Partial Discharge test both before and after bending test should be incorporated within the acceptance test.

Miscellaneous Agenda 1: Incorporation Polycarbonate encapsulation for LTCT –

Proposed Modifications:

Use of Polycarbonate encapsulation as insulating medium for 200/5 & 400/5 amp LTCT used for metering purpose of LT bulk consumers.

Discussions:

1. At present the Tape wound CT is being used for LT bulk consumers.
2. The tape used for insulating the LTCT may degrade over time, as it is susceptible to moisture ingress. It may lead to the degradation of the insulation of the LTCT.
3. The pros cons of the polycarbonate encapsulation as a insulating medium for LTCT is discussed.
4. OEM observations on polycarbonate encapsulation are also discussed.

Resolution of the Committee:

1. It is decided that the polycarbonate encapsulation may be accepted as insulating medium for LTCT in addition to the existing tape wound LTCT to assess its performance.
2. One separate specification of polycarbonate encapsulated LTCT has been prepared and signed.

20.12.26
Superintending Engineer (E)
Procurement & Contract Deptt.
WBSEDCL
Vidyut Bhavan, Kolkata-700 091

D Chowdhury
CE:P&E-Dist
26/01/26

A K Mallik
CE: DTD
26/01/26

S G Dutta
CE:R&CD
26/01/26

T Halder
CE:Dist(South)
26/01/26

M Mukhopadhyay
ACE: P&E
26/01/26

B Saha
ACE:P&CD
26/01/26

A Makur
ACE:DTD
26/01/26

R C Madhu
ACE:P&CD
26/01/26

S Ghosh
ACE: P&E
26/01/26

P Bhattacharya
SE:P&CD
26/01/26

A Biswas
SE:DTD
26/01/26

S Ray
SE:P&E
26/01/26

P Pal
SE: Dist HQ
26/01/26

S Ray
DE:P&E
26/01/26

S Das
DE:P&CD
26/01/26